



Ford Charge Station Pro

Application	Home
Current, Rated (AC)	80A
Voltage, Rated (VAC)	208 / 240VAC
Max Power	19.2kW @ 240VAC 16.6kW @ 208VAC
Type	AC, Level 2 and DC
Connector	CCS-1
Wiring	L1, L2, Gnd
Wiring Type	Hardwired
Current De-Rate Options (Amps AC)	64, 48, 40, 32, 16, 12
Cable Length	25ft 7.4m
Bluetooth	Yes*
Cellular	No
Wifi	Yes* 802.11 b/g/n
Ethernet	No
Home Integration System / Intelligent Backup Power Compatible	Yes (US Only)
Communication	OCPP 1.6J
HMI	LED Status Indicators
Dimensions (HxWxD)	23.4 x 12.7 x 7in 36 x 33 x 18 cm
Operating Temperature	-40° F to 113° F -40° C to 140° C
Temperature Range (Storage)	-40° F to 140° F -40° C to 60° C
Key Standards and Certifications	US & Canada UL File #: E522055

Environmental	NEMA 4
Altitude	9840ft/3000m
Operating Humidity	98% non-condensing
Mounting	Wall Only
Wiring Interfaces	Bottom or Back
Certifications	US, Canada
Energy Star	No
Warranty	3yr**



*Download Ford Charge Station Pro Setup App and follow prompts.

**Includes parts and on-site labor.

1 The Limited Warranty is being provided by Ford to the person or entity who purchased the Product from Ford ("Buyer") and, subject to the product terms and conditions, covers any defect in the Product which can be directly and exclusively attributed to design, workmanship or material defect of the Product for a period of three (3) years after the Warranty Starting Date. Warranty start date is the date of shipment unless installed at a commercial location by a Ford Pro Designated Installer. If Ford Pro Designated installed, the start date is the earlier of: (i) the date the Product is installed at the Buyer's site; or (ii) the date that is six (6) months after the date the Product is shipped to Buyer. Other conditions apply.

2 Technical information subject to change.